BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2022-23 Dated: 26-08-2022

APPROVED TENDER SCHEDULE –'B'

Item 31

e of Work:-Repairs and maintenance of Footpaths in Someshwara ward no -03 of yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri Manoj Naik B M	
				Rate	Rate in Words
1	Removing and resetting of Cobble Stone	Sqm	367.75	588.45	Five Hundred EightyEight Paise FourtyFive Only
2	Removing and resetting of Kerb Stone	Sqm	281.96	121.23	One Hundred TwentyOne Paise TwentyThree Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The Granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	86.86	5706.18	Five Thousand Seven Hundred Six Paise Eighteen Only
4	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications.	Sqm	157.61	1116.78	One Thousand One Hundred Sixteen Paise SeventyEight Only
5	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) 600 x 300 x 150 mm Kerb Stone	Nos	269.00	473.54	Four Hundred SeventyThree Paise FiftyFour Only
6	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	352.45	87.33	EightySeven Paise ThirtyThree Only

Manoj Naik

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

	ing and fixing precast reinforced cement concrete ing slabs of 10Cm thick made of M25 with OPC ent,@340kgs/cum with 20mm and down size graded ite metal coarse aggregate @0.70cum and fine gregate & 0.74 cum with superplasticizer achine,mixed, Inculding providing and removing entering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	257.40	1935.25	One Thousand Nine Hundred ThirtyFive Paise TwentyFive Only
	Providing and fixing precast reinforced cement concrete covering slabs of 23Cm thick made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.	Sqm	169.20	4704.56	Four Thousand Seven Hundred Four Paise FiftySix Only

Signature of the
Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.